COUNT CRAWFORD

STANDARD ROAD PLANS


THE FOLLOWING STANDARD ROAD PLANS SHALL BE CONSIDERED APPLICABLE TO CONSTRUCTION WORK ON THIS PROJECT.

| IDENT. | DATE | IDENT. | DATE | IDENT. | DATE |
|---------|----------|--------|----------|--------|----------|
| RC-15A | 04-20-04 | RE-64B | 10-19-04 | RL-1A | 10-03-00 |
| RC-16B | 04-20-04 | RE-68 | 10-19-04 | RL-18 | 10-03-00 |
| | | RE-69C | 10-19-04 | RL-7 | 12-03-96 |
| | | RE-76 | 10-21-03 | RL-14 | 01-12-99 |
| . RE-28 | 04-03-01 | | | RL-16 | 10-19-04 |
| RE-7 | 04-15-03 | RF-5 | 10-03-00 | | |
| RE-12A | 10-19-04 | RF-30A | 0328-95 | RS-26A | 10-28-97 |
| RE-128 | 10-19-04 | RF-32 | 03-28-95 | | |
| RE-47 | 10-19-04 | RF-33 | 03-28-95 | | |
| RE-48A | 10-19-04 | | | • | |

PROJECT TRAFFIC CONTROL PLAN

THIS ROAD WILL BE CLOSED TO THROUGH TRAFFIC DURING CONSTRUCTION. LOCAL TRAFFIC TO ADJACENT PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.08 OF THE CURRENT STANDARD SPECIFICATIONS. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, SIGNING, AND PAVEMENT MARKINGS INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATIVE CODE (IAC) CHAPTER 130.

THIS PROJECT (COE #2004-712) IS COVERED BY U.S. ARMY CORPS OF ENGINEERS NATIONWIDE PERMIT #'s 13, 14 & 33.



IOWA DEPARTMENT OF TRANSPORTATION Highway Division

PLANS OF PROPOSED IMPROVEMENT ON THE

FARM TO MARKET SYSTEM

PROJECT NO. BROS-C024(66)--5F-24

BRIDGE AND APPROACHES - PPCB

APPROXIMATELY 9 MILES WEST OF DENISON ON COUNTY ROAD E46 OVER A SMALL STREAM

THE IOWA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2001, PLUS APPLICABLE GENERAL SUPPLEMENTAL SPECIFICATIONS, DEVELOPMENTAL SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS SHALL APPLY TO CONSTRUCTION WORK ON THIS PROJECT.

THIS PROJECT IS COVERED BY THE IOWA DEPARTMENT OF NATURAL RESOURCES NPDES GENERAL PERMIT NO. 2. THE CONTRACTOR SHALL CARRY OUT THE TERMS AND CONDITIONS OF GENERAL PERMIT NO. 2 AND THE STORM WATER POLLUTION PREVENTION PLAN WHICH IS A PART OF THESE CONTRACT DOCUMENTS. REFER TO SECTION 2602 OF THE STANDARD SPECIFICATIONS FOR ADDITIONAL INFORMATION.

> DIVISION I-BRIDGE **DIVISION II - GRADING**

| | MILEAGE SUMMARY | | |
|------|---------------------------------------|---------|--------|
| DIV. | LOCATION | LIN.FT. | MILES |
| | STA. 112+25.00 TO STA. 121+50.85 | 925.85 | 0.1754 |
| ۱ ۱ | BRIDGE AT STA. 116+25.00 | 154.33 | 0.0292 |
| II | TOTAL NET LENGTH OF PROJECT (GRADING) | 771.52 | 0.1461 |

2000, TRAFFIC COUNT = 50 V.P.D.

ALL SHOP DRAWINGS AND FALSEWORK DRAWINGS THAT REQUIRE APPROVAL SHALL BE SUBMITTED TO AND APPROVED BY THE CONTRACTOR, WHO SHALL THEN SUBMIT THEM TO CALHOUN-BURNS AND ASSOCIATES, INC., FOR REVIEW AND APPROVAL.

CRAWFORD COUNTY

1801 FULLER ROAD, P.O. BOX 65859 WEST DES MOINES, IOWA 50265 TELEPHONE : (515) 224-4344

These shop grayings shall $\underline{\text{NOT}}$ be sent to lowa d.g.t. office of bridges and structures.

PROJECT NO. BROS-C024(66)--5F-24 FHWA NO. 128090

INDEX OF SHEETS

- TITLE SHEET
- QUANTITY SUMMARY DIVISION !
- QUANTITY SUMMARY DIVISION II

DIVISION I - $151'-4 \times 24'-6$ P.P.C.B. BRIDGE


- SITUATION PLAN
- GENERAL NOTES AND POLLUTION PREVENTION PLAN
- SOUNDING DATA
- SUPERSTRUCTURE DETAILS
- SUBSTRUCTURE DETAILS AND STAKING DIAGRAM

DIVISION II - GRADING

- GRADING NOTES AND TYPICAL SECTIONS
- **TABULATIONS** 10.
- PLAN AND PROFILE 11.
- CROSS SECTIONS 12.-15.

| IOWA | DEPARTMENT OF TRANSF STANDARDS REQUIRED | |
|-----------|--|-----------------|
| STANDARD | DATE ISSUED | LATEST REVISION |
| H24-87 | JANUARY, 1987 | - |
| H24-1-87 | JANUARY, 1987 | 1-1-88 |
| H24-2-87 | JANUARY, 1987 | |
| H24-3-87 | JANUARY, 1987 | 1-1-89 |
| H24-13-87 | JANUARY, 1987 | 1-1-89 |
| H24-15-87 | JANUARY, 1987 | 6-89 |
| H24-16-87 | JANUARY, 1987 | - |
| H30-14-94 | JANUARY, 1994 | |
| H3D-15-94 | JANUARY, 1994 | - |
| P1 0A | AUGUST, 1988 | 8-1-96 |

THESE SHEETS MAY BE OBTAINED AT THE OFFICE OF LOCAL SYSTEMS.




HEREBY CERTIFY THAT THIS ENGINEERING DOCUMENT WAS PREPARED BY ME OR UNDER MY DIRECT PERSONAL SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE

DATE: 7-73-04 LOWELL G. MILLER. P.E.

MY LICENSE RENEWAL DATE IS DECEMBER 31, 2004


PAGES OR SHEETS COVERED BY THIS SEAL:




I HEREBY CERTIFY THAT THIS ENGINEERING DOCUMENT WAS PREPARED BY ME OR UNDER MY DIRECT PERSONAL SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE

DATE: 7/23/04 MY LICENSE RENEWAL DATE IS DECEMBER 31, 2004

PAGES OR SHEETS COVERED BY THIS SEAL:





Highway Division

ACCEPTED FOR LETTING

8/31/04 DISTRICT LOCAL DATE SYSTEMS ENGINEER

TOTAL ESTIMATED QUANTITIES - DIVISION I 151'-4 x 24'-6 P.P.C.B. BRIDGE

| REF. | NO. | CODE NO. | ITEM | UNIT | 2 ABUTS | 2 PIERS | SUPERST. | TOTAL |
|------|-----|---------------|--|---------|-----------|---------|----------|--------|
| 1 | | 2104-2710020 | EXCAVATION, CLASS 10, CHANNEL | CU.YDS. | - | - | _ | 3,071 |
| 2 | | 2401-6745650° | REMOVAL OF EXISTING STRUCTURES | LS. | | 1 | | 1 1 |
| 3 | | 2402-2720000 | EXCAVATION, CLASS 20 | CU.YDS. | <i>73</i> | 1 | | 73 |
| 4 | | 2403-0100010 | STRUCTURAL CONCRETE (BRIDGE) | CU,YDS. | 21.6 | 17.8 | 140.7 | 180.1 |
| 5 | | 2404-7775000 | REINFORCING STEEL | LBS. | 3,292 | 1,986 | 39,665 | 44,943 |
| 6 | | 2407-0580146 | BEAMS, PRETENSIONED PRESTRESSED CONCRETE, LXA46 | EACH | _ | _ | 8 | 8 |
| 7 | | 24070580155 | BEAMS, PRETENSIONED PRESTRESSED CONCRETE, LXA55 | EACH | _ | | 4 | 4 |
| 8 | | 2408-7800000 | STRUCTURAL STEEL | LBS. | | | 2,403 | 2,403 |
| 9 | | 2414-6424120 | CONCRETE OPEN RAILING | LIN.FT. | _ | - | 336.7 | 336.7 |
| 10 | , | 2501-5425042 | PILES, DRIVE STEEL BEARING, HP 10x42; 10 @ 70' | LIN.FT. | 700 | _ | - | 700 |
| 11 | , | 2501-5425053 | PILES, DRIVE STEEL BEARING, HP 12x53; 14 @ 75' | LIN.FT. | | 1,050 | | 1,050 |
| 12 | ? | 2501-5475053 | CONCRETE ENCASEMENT OF STEEL H-PILES, HP 12x53 (P10A TYPE 3); 14 @ 26' | LIN.FT. | _ | 354 | | 364 |
| 13 | 3 | 2501-5550042 | PILES, FURNISH STEEL BEARING, HP 10x42; 10 @ 70" | LIN.FT. | 700 | _ | _ | 700 |
| 14 | 1 | 2501-5550053 | PILES, FURNISH STEEL BEARING, HP 12x53; 14 @ 75' | LIN.FT. | _ | 1,050 | - | 1,050 |
| 15 | 5 | 2501-6335010 | PREBORED HOLES, 10 @ 10' | LIN.FT. | 100 | - | _ | 100 |
| 16 | ; | 2507-3250005 | ENGINEERING FABRIC | SQ.YDS. | _ | - | | 2,010 |
| 17 | , | 2507-6800061 | REVETMENT, CLASS 'E' | TONS | _ | _ | | 1,425 |
| 18 | 3 | 2533-4980005 | MOBILIZATION | L.S. | _ | | _ | 1 |
| | | | | | | | | |

ESTIMATE REFERENCE INFORMATION REF. NO.

INCLUDES COSTS TO CLEAR THE CHANNEL TO THE SHAPE, DEPTH, AND EXTENT SHOWN IN THE "LONGITUDINAL SECTION ALONG CENTERLINE OF ROADWAY" AND THE LIMITS SHOWN ON THE "SITUATION PLAN." APPROXIMATELY 710 C.Y. OF SUITABLE CLASS 10 CHANNEL MATERIAL SHALL BE USED TO SHAPE THE CHANNEL.

INCLUDES COST OF USING APPROXIMATELY 1,740 C.Y. OF SUITABLE MATERIAL FOR CONSTRUCTION OF APPROACH ROADWAY. GUARDRAIL BERMS, AND ENTRANCES IN ACCORDANCE WITH I.D.O.T. ROAD STANDARD RL-1A OR RL-1B SUITABLE SOILS SHALL BE AS DEFINED BY ARTICLE 2102.06 PARAGRAPH A2 OF THE STANDARD SPECIFICATIONS. UNSUITABLE OR EXCESS MATERIAL SHALL BE

THE EXISTING BRIDGE IS A 60'x 20.2' RIVETED STEEL PONY TRUSS WITH TWO I-BEAM APPROACHES (A TOTAL LENGTH OF 116'). 2. HIGH TIMBER ABUTMENTS AND TIMBER PIERS. THE STRUCTURE HAS A TIMBER DECK.

THE LUMP SUM BID FOR "REMOVAL OF EXISTING STRUCTURES" SHALL INCLUDE REMOVAL AND DISPOSAL OF THE EXISTING STRUCTURE AND THE DRIFT PILE N.E. OF THE BRIDGE, THE STEEL I-BEAMS FROM THE APPROACHES AND TRUSS SPANS SHALL REMAIN THE PROPERTY OF THE COUNTY AND THE CONTRACTOR SHALL CAREFULLY REMOVE AND NEATLY STACK THESE ITEMS WITHIN THE RIGHT-OF-WAY. ALL REMAINING SALVAGEABLE MATERIAL AND UNSALVAGEABLE MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR. THE EXISTING STRUCTURE SHALL BE REMOVED TO AN ELEVATION AT LEAST 1' & BELOW FINISHED GROUNDLINE AND TO THE EXTENT THAT IT WILL NOT INTERFERE WITH THE NEW CONSTRUCTION.

SEE HAZARDOUS MATERIAL NOTES, SHEET 5, FOR PAINT SCRAPE SAMPLE RESULTS.

- INCLUDES COSTS OF USING SUITABLE CLASS 20 EXCAVATION TO CONSTRUCT GUARDRAIL BERMS AND APPROACH FILLS IN 3. ACCORDANCE WITH I.D.O.T. ROAD STANDARD RL-1A OR RL-1B. UNSUITABLE OR EXCESS MATERIAL SHALL BE WASTED ON SITE. QUANTITY IS BASED ON THE ASSUMPTION THAT CHANNEL EXCAVATION AND NECESSARY BERM CONSTRUCTION HAVE BEEN
- ALL STRUCTURAL CONCRETE FOR THE BRIDGE DECK IS TO BE CLASS "C"; SUBSTITUTION OF CLASS "D" CONCRETE IS NOT ALLOWED.

INCLUDES COST OF TAR PAPER AND PREFORMED JOINT MATERIAL.

NO ADDITIONAL PAYMENT WILL BE ALLOWED FOR HEATING AND PROTECTION OF CONCRETE, IF NECESSARY. CERTIFIED PLANT INSPECTION IS REQUIRED.

NUMBER OF PILES AND BEARING CAPACITY PER PILE AT ABUTMENTS IS BASED ON BEARING NOT LISTED IN BRIDGE STANDARD H24-2-87 FOR THIS LENGTH BRIDGE. CONTRACTOR IS TO NOTE RESULTING CHANGES TO SOME REINFORCING STEEL ITEMS. THE REINFORCING STEEL QUANTITY TABULATIONS ON I.D.O.T. H24-2-87 FOR ABUTMENTS WITH FOUR (4) POINT BEARING PILES SHALL BE REVISED TO USE FIVE (5) STEEL H- PILES USING FRICTION BEARING FOR THE FOLLOWING ITEMS:

612188 88 - 4p1 HOOPS 10 - PILE SPIRALS **64 LBS** 20 - PILE SPIRALS SPACERS 25 LBS.

THE REVISED SUBTOTAL FOR REINFORCING STEEL IS: 35,718 LBS. - 51 LBS. + 64 LBS. - 20 LBS. + 25 LBS. = 35,736 LBS. ALL REINFORCING SHALL BE GRADE 60.

INCLUDES COST OF BEARING MATERIAL, COIL TIES AND COIL RODS. 6.-7. COARSE AGGREGATE FOR PRESTRESSED CONCRETE BRIDGE UNITS SHALL MEET THE REQUIREMENTS OF SECTION 4115 CLASS III DURABILITY, GRADATION OF THE COARSE AGGREGATE SHALL MEET THE REQUIREMENTS OF SECTION 2407.02A.

INCLUDES COST OF STEEL DIAPHRAGMS, SEE STANDARD SHEET H24-13-87.

CERTIFIED PLANT INSPECTION IS REQUIRED.

9.

12.

15.

16.

17.

18.

THE PILING ENCASEMENTS ARE TO EXTEND DOWN TO THE ELEVATIONS SHOWN ON THE SITUATION PLAN, SHEET 4. THE UNIT PRICE BID FOR ENCASEMENT SHALL BE FULL PAYMENT FOR FURNISHING AND PLACING MATERIAL AND, WHERE NECESSARY, EXCAVATION.

SEE STANDARD P10A REVISED AUGUST 1, 1996 FOR DETAILS.

THE CONTRACTOR SHALL PREBORE HOLES FOR ABUTMENT PILES. MINIMUM DIAMETER OF THE HOLES SHALL BE 18 INCHES. HOLES SHALL BE BORED TO ELEVATIONS SHOWN ON THE "LONGITUDINAL SECTION ALONG CENTERLINE" ON "THE SITUATION PLAN" SHEET 4. HOLES SHALL BE FILLED WITH A NATURAL BENTONITE SLURRY. PILES SHALL BE DRIVEN THROUGH THE HOLES TO AT LEAST THE SPECIFIED DESIGN BEARING. FOR HOLES DRILLED IN NONCOLLAPSING SOILS THE BENTONITE SLURRY MAY BE PLACED AFTER PILES ARE DRIVEN; IN COLLAPSING SOILS THE BENTONITE SLURRY SHALL BE PLACED AT THE TIME THE HOLE IS DRILLED. INCLUDES ALL LABOR AND MATERIALS FOR FURNISHING AND PLACING THE BENTONITE SLURRY.

SEE "SITUATION PLAN, SHEET 4 FOR LIMITS.

REVETMENT IS TO BE PLACED AT A THICKNESS OF 1'-6. SEE "SITUATION PLAN, SHEET 4 FOR LIMITS THE UNIT PRICE BID FOR "REVETMENT, CLASS E" SHALL INCLUDE COST OF LABOR, EQUIPMENT, AND MATERIALS REQUIRED TO PLACE CLASS E REVETMENT STONE ON CHANNEL BANKS IN ACCORDANCE WITH SECTION 2507 OF THE STANDARD SPECIFICATIONS.

INCLUDES MOBILIZATION FOR BOTH DIVISION I AND DIVISION II.

151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

INTERGAL ABUTMENTS 47'-5 END SPANS

P10A PIERS 56'-6 INTERIOR SPAN

QUANTITY SUMMARY - DIVISION I

STATION 116+25.00 CRAWFORD COUNTY,

TOTAL ESTIMATED QUANTITIES : DIVISION II **GRADING**

| REF. | CODE NO. | ITEM | UNIT | TOTAL |
|------|--------------|--|---------|--------|
| 19 | 2101-0850001 | CLEARING AND GRUBBING | ACRES | 0.21 |
| 20 | 2101-0850002 | CLEARING AND GRUBBING | UNITS | 40 |
| 21 | 2102-2710070 | EXCAVATION, CLASS 10, ROADWAY AND BORROW | CU.YDS. | 14,568 |
| 22 | 2312-8260051 | GRANULAR SURFACING ON ROAD, CLASS 'A' CRUSHED STONE | TONS | 320 |
| 23 | 2417-0225024 | APRONS, METAL, 24 IN. DIA. | EACH | 2 |
| 24 | 2417-0225030 | APRONS, METAL, 30 IN. DIA. | EACH | 2 |
| 25 | 2417-1040024 | CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA. | LIN.FT. | 32 |
| 26 | 2417-1040030 | CULVERT, CORRUGATED METAL ENTRANCE PIPE, 30 IN. DIA. | LIN.FT. | 30 |
| 27 | 2505-4008200 | INSTALLATION OF GUARDRAIL | LIN.FT. | 275 |
| 28 | 2505-4021690 | GUARDRAIL, END ANCHORAGE, BEAM, RE-69 | EACH | 4 |
| 29 | 2505-4021762 | CUARDRAIL TERMINAL, BEAM, FLARED RE-76 | EACH_ | 4 |
| 30 | 2518-6910000 | SAFETY CLOSURE | EACH | 4 |
| 31 | 2528-8445110 | TRAFFIC CONTROL | L.S. | 1 |
| 32 | 2601-2632110 | FERTILIZING | ACRE | 2.45 |
| 33 | 2601-2634100 | MULCHING | ACRE | 2.45 |
| 34 | 2601-2636015 | NATIVE GRASS SEEDING | ACRE | 2.45 |
| 35 | 2602-0000020 | SILT FENCE | LIN.FT. | 820 |
| 36 | 2602-0000030 | SILT FENCE FOR DITCH CHECKS | LIN.FT. | 80 |
| 37 | 2602-0000090 | CLEAN-OUT OF SILT FENCE | LIN.FT. | 700 |
| 38 | 2602-0000100 | CLEAN-OUT OF SILT FENCE FOR DITCH CHECKS | LIN.FT. | 80 |

REF. NO. ESTIMATE REFERENCE INFORMATION

21.

SEE PLAN AND PROFILE SHEET FOR LIMITS AND LOCATIONS. UNIT MEASUREMENTS WILL BE MADE AT THE TIME OF 19-20. CONSTRUCTION.

SELECTIVE CLEARING WILL BE REQUIRED ON THIS PROJECT. ALL DESIRABLE TREES OUTSIDE THE CONSTRUCTION AREA WILL BE SAVED.

THE APPROACH BERMS SHALL BE BUILT TO THE CONSTRUCTION LIMITS SHOWN AND SHALL BE IN PLACE BEFORE ABUTMENT PILES ARE DRIVEN. THE CONTRACTOR SHALL LEVEL AND SHAPE THE BERMS TO THE ELEVATIONS AND DIMENSIONS SHOWN ON THE SITUATION PLAN. DRESSING OF SLOPES OUTSIDE THE BRIDGE AREA NOT DISTURBED BY THE CONTRACTOR WILL BE PAID FOR AS EXTRA WORK.

ROADWAY CONSTRUCTION REQUIRES 16,308 C.Y. OF FILL MATERIAL. OF THIS, 1,520 C.Y. IS AVAILABLE FROM DITCH CUTS AND 1,740 C.Y. IS AVAILABLE FROM, AND WILL BE PAID AS, "EXCAVATION, CLASS 10, CHANNEL". THE REMAINING 13,048 C.Y. IS TO BE FURNISHED AS BORROW. TYPE "A" COMPACTION WILL BE REQUIRED. SEE TABULATIONS AND PLAN AND PROFILE SHEETS FOR BREAKDOWN OF EXCAVATION QUANTITIES. INCLUDES MATERIAL FOR INTERSECTIONS, BRIDGE APPROACHES AND ENTRANCES. THE QUANTITY INCLUDES AN ADDITIONAL 35% TO COMPENSATE FOR SHRINKAGE.

THE CONTRACTOR IS TO PROVIDE HIS OWN BORROW FOR "CLASS 10, ROADWAY AND BORROW, EXCAVATION. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH PROVISIONS OF IOWA LAW AS IT APPLIES TO REMOVAL AND REPLACEMENT OF TOPSOIL ON BORROW AREAS.

NO PAYMENT FOR OVERHAUL SHALL BE MADE ON THIS PROJECT.
PAY QUANTITY WILL BE PLAN QUANTITY ADJUSTED FOR OBVIOUS ERRORS, PLAN REVISIONS OR CHANGE ORDERS.

EXCEPT WHERE NOTED OTHERWISE ON THE PLANS, ALL ENTRANCE AND ROADWAY CULVERTS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AS PART OF "EXCAVATION, CLASS 10, ROADWAY AND BORROW".

MOISTURE SHALL BE APPLIED, AS NECESSARY, TO THE CONSTRUCTION AREA TO PREVENT THE SPREAD OF DUST NEAR RESIDENTIAL AREAS AND INDIVIDUAL HOMES. REFER TO ARTICLE 1107.07 OF THE STANDARD SPECIFICATIONS FOR ADDITIONAL DETAILS.

- SURFACING TO BE FURNISHED AND PLACED BY THE CONTRACTOR IN TWO PASSES (1400 AND 600 TONS /MILE). 22. INCLUDES 10 TONS FOR DRIVES AND 15 TONS FOR INTERSECTION.
- SEE TABULATIONS, SHEET 10. 23-24.
- SEE TABULATIONS, SHEET 10. 25-26.

ALL PIPE SHALL BE STANDARD CORRUGATIONS, NO HELICALLY CORRUGATED PIPE WILL BE ALLOWED. ALL CONNECTING BANDS SHALL BE 24" WIDE.

- SEE TABULATIONS, SHEET 10 AND STANDARD ROAD PLANS. 27-29.
- SEE TABULATIONS, SHEET 10 30.
- SEE SHEETS 1 AND 10. 31.
- THE CONTRACTOR IS TO RESHAPE, FERTILIZE, SEED AND MULCH ANY AREAS DISTURSED DURING CONSTRUCTION TO THEIR 32-34 ORIGINAL CONDITION. THIS SHALL BE INCLUDED IN THE PRICES BID FOR "NATIVE GRASS SEEDING", "FERTILIZING" AND "MULCHING,"
- SEE TABULATIONS, SHEET 10. 35-38


151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

INTERGAL ABUTMENTS

P10A PIERS 56'-6 INTERIOR SPAN

QUANTITY SUMMARY - DIVISION II

STATION 116+25.00 CRAWFORD COUNTY,



DESIGN: AASHTO SERIES OF 1983, PLUS INTERIM SPECIFICATIONS.

CONSTRUCTION: STANDARD SPECIFICATION OF THE IOWA DEPARTMENT OF TRANSPORTATION, HIGHWAY DIVISION, SERIES OF 2001, PLUS APPLICABLE GENERAL SUPPLEMENTAL SPECIFICATIONS, DEVELOPMENTAL SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS SHALL APPLY TO CONSTRUCTION WORK ON THIS PROJECT.

DESIGN STRESSES

DESIGN STRESSES FOR THE FOLLOWING MATERIALS ARE IN ACCORDANCE WITH AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, SERIES OF 1983, PLUS INTERIM

| CONCRETE | SECTION 8 | ľС | = | 3,500 PSI |
|----------------------|----------------------|----|---|------------|
| REINFORCING STEEL | SECTION 8 | | | |
| ASTM A615 | GRADE 60, | fs | = | 24,000 PSI |
| PRESTRESSING STEEL | SEE SHEETS H30-14-94 | | | |
| PRESTRESSED CONCRETE | SEE SHEETS H30-14-94 | | | |
| STRUCTURAL STEEL | SECTION 10 | | | |
| ASTM A36 | | ſS | = | 20,000 PSI |

GENERAL NOTES

THIS DESIGN IS FOR A 151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE ON COUNTY ROAD E-46 OVER A SMALL STREAM IN CRAWFORD COUNTY, IOWA.

THIS BRIDGE IS DESIGNED FOR HS20-44 LOADING PLUS 20 LBS. PER SQ. FT. OF ROADWAY FOR FUTURE WEARING SURFACE.

ACCESS SHALL BE MAINTAINED TO INDIVIDUAL PROPERTIES DURING CONSTRUCTION. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.

THE CONTRACTOR IS RESPONSIBLE FOR CONDUCTING AN INDEPENDENT CHECK OF ALL CONSTRUCTION STAKES PLACED FOR THE PROJECT. THIS INDEPENDENT CHECK SHALL BE SUFFICIENT TO UNDERSTAND THE PLACEMENT AND INTENT OF THE STAKES.

THE CONTRACTOR SHALL NOTE THAT THIS IS A STRAIGHT BRIDGE LOCATED ON A HORIZONTAL CURVE. SEE SHEET 8 FOR STAKING DIADRAGM

THIS PROJECT IS TO BE BUILT UNDER THE CONDITIONS OF ARMY CORPS OF ENGINEERS 404 PERMIT NUMBER 2004-712. THIS IS A NATIONWIDE PERMIT AND MAY CONTAIN SPECIAL CONDITIONS. WORK REQUIRED UNDER THIS PERMIT IS CONSIDERED INCIDENTAL TO OTHER WORK. A COPY OF THE PERMIT IS AVAILABLE AT THE COUNTY ENGINEER'S OFFICE. THE ARMY CORPS OF ENGINEERS RESERVES THE RIGHT TO VISIT THE SITE WITHOUT PRIOR

THE CONTRACTOR IS ENCOURAGED TO TAKE FULL ADVANTAGE OF SPECIFICATION 1105.15 - VALUE ENGINEERING INCENTIVE PROPOSAL, A PAMPHLET AND CONCEPTUAL PROPOSAL FORM WILL BE AVAILABLE AT THE PRECONSTRUCTION CONFERENCE.

STANDARD ROAD PLANS ARE AVAILABLE FROM THE IOWA DEPARTMENT OF TRANSPORTATION, HIGHWAY DIVISION, AMES, IOWA.

ARTICLE 2317 REGARDING BRIDGE DECK SMOOTHNESS DOES NOT APPLY TO THIS PROJECT.

UTILITY NOTES

THE CONTRACTOR SHALL VISIT THE CONSTRUCTION SITE TO ENSURE THAT HE IS FAMILIAR WITH THE EXISTING SITE CONDITIONS. THE CONTRACTOR WILL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE OWNERS OF ALL UTILITIES PRIOR TO THE BEGINNING OF CONSTRUCTION. ACCESS SHALL BE AFFORDED TO THESE FACILITIES FOR NECESSARY MODIFICATION OF SERVICES.

UNDERGROUND FACILITIES, STRUCTURES AND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS. THEREFORE, THEIR LOCATIONS MUST BE CONSIDERED APPROXIMATE ONLY, IT IS POSSIBLE THERE ARE OTHERS, THE EXISTENCE OF WHICH IS NOT PRESENTLY KNOWN OR SHOWN. SHOULD ANY UTILITIES BE FOUND, THEY SHALL BE PROTECTED IN PLACE AND THE ENGINEER IMMEDIATELY NOTIFIED. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES.

NO CLAIMS FOR ADDITIONAL COMPENSATION WILL BE ALLOWED TO THE CONTRACTOR FOR INTERFERENCE, OR DELAY CAUSED BY UTILITY COORDINATION OR RELOCATION WORK.

WASTE AND DISPOSAL NOTES

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE WASTE AREAS OR DISPOSAL SITES FOR EXCESS MATERIAL (EXCAVATED MATERIAL OR BROKEN CONCRETE) WHICH IS NOT DESIRABLE TO BE INCORPORATED INTO THE WORK INVOLVED ON THIS PROJECT. THESE AREAS SHALL NOT IMPACT WETLANDS OR "WATERS OF THE U.S." NO PAYMENT FOR OVERHAUL WILL BE ALLOWED FOR MATERIAL HAULED TO THESE SITES. NO MATERIAL SHALL BE PLACED WITHIN THE RIGHT-OF-WAY AND SHALL NOT CREATE AN

HAZARDOUS MATERIALS NOTES

A SCRAPE SAMPLE OF THE EXISTING PAINT WAS TAKEN TO GET AN INDICATION OF THE EXISTENCE AND LEVEL OF TOTAL CHROMIUM AND TOTAL LEAD. SAMPLE ANALYSIS OF TOTAL LEAD ON THIS SAMPLE WAS 1,440 MG/KG AND TOTAL CHROMIUM ON THIS SAMPLE WAS 30,000 MG/KG. THIS ANALYSIS SHOWS THE EXISTENCE OF THESE TWO TOXIC CONSTITUENTS. LEVELS INDICATED BY THESE TESTS COULD CREATE CONDITIONS ABOVE REGULATORY LIMITS FOR HEALTH AND SAFETY REQUIREMENTS. NO OTHER CONSTITUENTS WERE ANALYZED. THE BIDDER SHOULD NOT RELY ON THE DEPARTMENT'S TESTING AND ANALYSIS FOR ANY PURPOSE OTHER THAN AS AN INDICATION OF THE EXISTENCE OF THESE TWO TOXIC

THE CONTRACTOR SHALL CONDUCT THEIR OPERATIONS IN SUCH A MANNER THAT ANY PAINT REMOVED DURING REMOVAL IS CONTAINED, COLLECTED, AND DISPOSED OF IN ACCORDANCE WITH ALL FEDERAL AND STATE REGULATIONS.

BEFORE DELIVERY OF ANY SCRAP STEEL THE CONTRACTOR SHALL PROVIDE A WRITTEN NOTICE TO THE RECEIVING FACILITY, THIS NOTICE SHALL AT A MINIMUM INCLUDE:

- 1. A NOTICE THAT THE SCRAP STEEL IS COATED WITH PAINT THAT HAS REGULATED MATERIALS AT LEVELS THAT COULD BE HAZARDOUS TO EMPLOYEES OR THE ENVIRONMENT.
- A COPY OF THE SCRAPE SAMPLE PROVIDED IN THE CONTRACT DOCUMENTS.
- A SIGNATURE BLOCK FOR THE RECEIVING FACILITY TO CONFIRM THEIR RECEIPT OF THIS INFORMATION

A COPY OF THIS NOTICE, SIGNED BY THE RECEIVEING FACILITY, SHALL BE RETURNED TO THE ENGINEER BEFORE ANY SCRAPE STEEL IS REMOVED FROM THE PROJECT. ALL COSTS ASSOCIATED WITH COMPLIANCE WITH THE ABOVE REMOVAL AND DISPOSAL REQUIREMENTS WILL BE INCIDENTAL TO "REMOVAL OF EXISTING STRUCTURES".

STREAM CROSSING NOTES

THE CONTRACTOR IS ENCOURAGED TO CONDUCT CONSTRUCTION ACTIVITIES DURING A PERIOD OF LOW FLOW. ANY TEMPORARY CROSSINGS SHALL INCLUDE ENOUGH CULVERTS TO ACCOMMODATE LOW FLOWS AND MUST BE REMOVED AFTER COMPLETION OF WORK ON THIS PROJECT. TEMPORARY STREAM CROSSINGS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD ROAD PLAN RL-16. THE COST OF INSTALLATION, MAINTENANCE, AND REMOVAL OF TEMPORARY CROSSINGS, INCLUDING CULVERTS, SHALL BE INCIDENTAL TO THE PROJECT.

EQUIPMENT FOR HANDLING AND CONVEYING MATERIALS DURING CONSTRUCTION SHALL BE OPERATED TO PREVENT DUMPING OR SPILLING THE MATERIAL INTO WATERBODIES, STREAMS OR WETLANDS EXCEPT AS APPROVED HEREIN.

CARE SHALL BE TAKEN TO PREVENT ANY PETROLEUM PRODUCTS, CHEMICALS, OR OTHER DELETERIOUS MATERIALS FROM ENTERING WATERBODIES, STREAMS OR WETLANDS. CONSTRUCTION EQUIPMENT, ACTIVITIES, AND MATERIALS SHALL BE KEPT OUT OF THE STREAMS AND WETLANDS TO THE MAXIMUM EXTENT POSSIBLE.

PILE NOTES

MINIMUM BEARING CAPACITY IS TO BE 43 TONS PER PILE AT PIERS AND 37 TONS PER PILE AT ABUTMENTS.

ALL PILES ARE TO BE DRIVEN TO FULL PENETRATION, WHERE PRACTICABLE,

SOUNDING AND TEST BORING DATA SHOWN ON PLANS WERE ACCUMULATED FOR DESIGNING AND ESTIMATING PURPOSES. THEIR APPEARANCE ON THE PLAN DOES NOT CONSTITUTE A GUARANTEE THAT CONDITIONS OTHER THAN THOSE INDICATED WILL NOT BE ENCOUNTERED.

CONCRETE AND REINFORCING STEEL NOTES

ALL REINFORCING STEEL SHALL BE SECURELY WIRED IN PLACE BEFORE CONCRETE IS PLACED. BAR CHAIRS SPACED AT NOT MORE THAN 3'-0 CENTERS IN EITHER DIRECTION SHALL BE USED TO SUPPORT ALL REINFORCING IN ACCORDANCE WITH THE SECTION 2404 OF THE STANDARD SPECIFICATIONS.

CLEAR DISTANCE FROM FACE OF CONCRETE TO NEAR REINFORCING BAR IS TO BE 2" UNLESS OTHERWISE NOTED OR SHOWN.

ALL EXPOSED CORNERS 90 DEGREES OR SHARPER ARE TO BE FILLETED WITH A 3/4" DRESSED AND BEVELED STRIP

CONCRETE PAVING BLOCKS ARE REQUIRED AND ARE TO REMAIN IN PLACE AFTER CONSTRUCTION

CONTRACTOR'S WORK AREA

THE CONTRACTOR'S WORK AND MATERIAL STORAGE AREA SHALL BE DEFINED BY THE CONTRACTOR AND NOTED TO THE ENGINEER. THE CONTRACTOR SHALL SHAPE, FERTILIZE. AND SEED THIS CONTRACTOR'S AREA IN ORDER TO RETURN IT TO ITS ORIGINAL CONDITION. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR "NATIVE GRASS SEEDING", FERTILIZING" AND "MULCHING" BID ITEMS. AREAS OUTSIDE THE CONTRACTOR'S AREA DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED TO THEIR ORIGINAL CONDITION, AS DETERMINED BY THE ENGINEER. NO ADDITIONAL PAYMENT WILL BE AUTHORIZED FOR



Request Utility Locate 48 Hours in Advance

POLLUTION PREVENTION PLAN

110-12A 10-29-02

POLLUTION PREVENTION PLAN

ALL CONTRACTORS/SUBCONTRACTORS SHALL CONDUCT THEIR OPERATIONS IN A MANNER THAT MINIMIZES EROSION AND PREVENTS SEDIMENTS FROM LEAVING THE HIGHWAY RIGHT-OF-WAY. THE PRIME CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE AND IMPLEMENTATION OF THE POLLUTION PREVENTION PLAN (FPP) FOR THEIR ENTIRE CONTRACT. THIS RESPONSIBILITY SHALL BE FURTHER SHARED WITH SUBCONTRACTORS WHOSE WORK IS A SOURCE OF POTENTIAL POLLUTION AS DEFINED IN THIS FPP.

SITE DESCRIPTION

THIS POLLUTION PREVENTION PLAN (PPP) IS FOR THE CONSTRUCTION OF A 1511-4 X 241-5 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE ON COUNTY ROAD E-46 OVER A SMALL STREAM IN CRAWFORD COUNTY, IOWA.

THIS PPP COVERS APPROXIMATELY 3.49 ACRES WITH AN ESTIMATED 3.49 ACRES BEING DISTURBED. THE PORTION OF THE PPP COVERED BY THIS CONTRACT HAS 3.49 ACRES DISTURBED.

THE PPP IS LOCATED IN AN AREA OF MONONA-IDA-HAMBURG SOIL ASSOCIATION. THE ESTIMATED AVERAGE NRCS RUNOFF CURVE NUMBER FOR THIS PPP AFTER COMPLETION WILL BE 51.

REFER TO THE PROJECT PLANS FOR LOCATIONS OF TYPICAL SLOPES, DITCH GRADES, AND MAJOR STRUCTURAL AND MON-STRUCTURAL CONTROLS. A COPY OF THIS PLAN WILL BE ON FILE AT THE COUNTY ENGINEER'S OFFICE. RUNOFF FROM THIS WORK WILL FLOW INTO A SMALL STREAM.

POTENTIAL SOURCES OF POLLUTION:
SITE SOURCES OF POLLUTION:
SITE SOURCES OF POLLUTION GENERATED AS A RESULT OF THIS WORK RELATE TO SILTS AND SEDIMENT WHICH MAY BE TRANSPORTED AS A RESULT OF A STORM EVENT. HOWEVER, THIS PPP PROVIDES CONVEYANCE FOR OTHER (NON-PROJECT RELATED) OPERATIONS. THESE OTHER OPERATIONS HAVE STORM WATER RUNOFF, THE REGULATION OF WHICH IS BEYOND THE CONTROL OF THIS PPP. POTENTIALLY THIS RUNOFF CAN CONTAIN VARIOUS POLLUTANTS RELATED TO SITE-SPECIFIC LAND USES. EXAMPLES ARE:

<u>rural agricultural activities;</u> Runoff from agricultural land use can potentially contain chemicals including herbicides, pesticides, fungicides

COMMERCIAL AND INDUSTRIAL ACTIVITIES:
RUNOFF FROM COMMERCIAL AND INDUSTRIAL LAND USE MAY CONTAIN CONSTITUENTS ASSOCIATED WITH THE SPECIFIC OPERATION.
SUCH OPERATIONS ARE SUBJECT TO POTENTIAL LEAKS AND SPILLS WHICH COULD BE COMMINGLED WITH RUN-OFF FROM THE
FACILITY. POLLUTANTS ASSOCIATED WITH COMMERCIAL AND INDUSTRIAL ACTIVITIES ARE NOT READILY AVAILABLE SINCE THEY ARE

CONTROLS

AT LOCATIONS WHERE RUNOFF CAN MOVE OFFSITE, SILT FENCE SHALL BE PLACED ALONG THE PERIMETER OF THE AREAS TO BE DISTURBED PRIOR TO BEGINNING GRADING, EXCAVATION OR CLEARING AND GRUBBING OPERATIONS. VEGETATION IN AREAS NOT NEEDED FOR CONSTRUCTION SHALL BE PRESERVED. AS AREAS REACH THEIR FINAL GRADE, ADDITIONAL SILT FENCES, SILT BASHIS, INTERCEPTING DITCHES, SOD FLUMES, LETDOWNS, BRIDGE END DRAINS, AND EARTH DIKES SHALL BE INSTALLED AS SPECIFIED IN THE PLANS ANDIOR AS REQUIRED BY THE PROJECT ENGINEER. THIS WILL INCLUDE USING SILT FENCE AS DITCH CHECKS AND TO PROTECT INTAKES. TEMPORARY STABILIZING SEEDING SHALL BE COMPLETED AS THE DISTURBED AREAS ARE CONSTRUCTED. IF CONSTRUCTION ACTIVITY IS NOT PLANNED TO COCCUR IN A DISTURBED AREA FOR AT LEAST 21 DAYS, THE AREA SHALL BE STABILIZED. TEMPORARY SEEDING OR MULCHING WITHIN 14 DAYS. OTHER STABILIZING METHODS SHALL BE USED OUTSIDE THE SEEDING TIME

THIS WORK SHALL BE DONE IN ACCORDANCE WITH SECTION 2502 OF THE STANDARD SPECIFICATIONS. IF THE WORK INVOLVED IS NOT APPLICABLE TO ANY CONTRACT ITEMS, THE WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 1109.03 PARAGRAPH B.

AS THE WORK PROGRESSES, ADDITIONAL EROSION CONTROLITEMS MAY BE REQUIRED AS DETERMINED BY THE ENGINEER AFTER FIELD INVESTIGATION. THESE MAY BE ITEMS SUCH AS LETDOWN STRUCTURES, SOIL STABILIZATION MATS AND OTHER APPROPRIATE MEASURES SHALL BE INSTALLED BY CONTRACTOR, AS DIRECTED BY THE ENGINEER. THE CONTRACTOR WILL COMPLETE THE CONSTRUCTION WITH THE ESTABLISHMENT OF PERMANENT PERENMIAL VEGETATION OF ALL DISTURBED AREAS.

OTHER CONTROLS

CONTRACTOR DISPOSAL OF UNUSED CONSTRUCTION MATERIALS AND CONSTRUCTION MATERIAL WASTES SHALL COMPLY WITH APPLICABLE STATE AND LOCAL WASTE DISPOSAL, SANITARY SEWER, OR SEPTIC SYSTEM REGULATIONS. IN THE EVENT OF A CONFLICT WITH OTHER COVERNMENTAL LAWS, RULES AND REGULATIONS, THE MORE RESTRICTIVE LAWS, RULES OR REGULATIONS

APPROVED STATE OR LOCAL PLANS:

DURING THE COURSE OF THIS CONSTRUCTION, IT IS POSSIBLE THAT SITUATIONS WILL ARISE WHERE UNKNOWN MATERIALS WILL BE ENCOUNTERED. WHEN SUCH SITUATIONS ARE ENCOUNTERED, THEY WILL BE HANDLED ACCORDING TO ALL FEDERAL, STATE, AND LOCAL REGULATIONS IN EFFECT AT THE TIME.

THE CONTRACTOR IS REQUIRED TO MAINTAIN ALL TEMPORARY EROSION CONTROL MEASURES IN PROPER WORKING ORDER, INCLUDING CLEANING, REPAIRING, OR REPLACING THEM THROUGHOUT THE CONTRACT PERIOD. CLEANING OF SILT CONTROL DEVICES SHALL BEGIN WHEN THE FEATURES HAVE LOST 50% OF THEIR CAPACITY.

INSPECTIONS SHALL BE MADE JOINTLY BY THE CONTRACTOR AND THE CONTRACTING AUTHORITY EVERY SEVEN CALENDAR DAYS AND AFTER EACH RAIN EVENT THAT IS ONE HALF INCH OR GREATER. THE CONTRACTOR SHALL IMMEDIATELY BEGIN CORRECTIVE ACTION ON ALL DEFICIENCIES FOUND. THE FINDINGS OF THIS INSPECTION SHALL BE RECORDED IN THE PROJECT DIARY. THIS PPP MAY BE REVISED BASED ON THE FINDINGS OF THE INSPECTION. THE CONTRACTOR SHALL IMPLEMENT ALL REVISIONS. ALL CORRECTIVE ACTIONS SHALL BE COMPLETED WITHIN 3 CALENDAR DAYS OF THE INSPECTION.

NON-STORM DISCHARGES

THIS INCLUDES SUBSURFACE DRAINS (I.E. LONGITUDINAL AND STANDARD SUBDRAINS), SLOPE DRAINS AND BRIDGE END ORAINS. THE VELOCITY OF THE DISCHARGE FROM THESE FEATURES MAY BE CONTROLLED BY THE USE OF PATIO BLOCKS, CLASS A STONE OR

151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

INTERGAL ABUTMENTS 47'-5 END SPANS

P10A PIERS 56'-6 INTERIOR SPAN

GENERAL NOTES AND POLLUTION PREVENTION PLAN

STATION 116+25.00 CRAWFORD COUNTY. O' SKEW IOWA

CALHOUN-BURNS & ASSOCIATES, INC. CONSULTING ENGINEERS WEST DES MOINES, IOWA 50265

CRAWFORD COUNTY

PROJECT NO. BROS-C024(66)--5F-24

SHEET 5 OF 15

BENCH MARK #1: 60d SPIKE IN GATE POST, SOUTH SIDE OF O AVENUE ROAD, OPPOSITE FARM DRIVE ENTRANCE TO HOUSE. 112+86, 34' RT., ELEV.= 482.31
BENCH MARK #2: RAILROAD SPIKE IN POWER POLE, 1st. POLE EAST OF BRIDGE, NORTH SIDE OF O AVENUE ROAD. 118+21, 34' LT., ELEV.= 471.73

| roject: | Beldg | t Q1 | an, B | 46 St. | Punk | Es T | 1 | STATION 115+49 3' LT Client: Calbona-Burns and Associates, Inc. 1801 Fuller Rand Wast Dan Moines, Jown 50265 | - | Z | Ž | .: 41340 |
|--|-------|-----------------|-------------|----------|------------------------|-------------------|--------------------------------------|---|----------|-------|-------------|---------------|
| Surface Datum: | Eleva | | | | 47. - 471. | | | Date Driffod: 7-1-04 Driffing Method: Driffing Depth, ft.: 65 Page: 1 of | 4" C | FA. | - | |
| Elevation ft. | Depth | Sample No. | Туре | SPT top/ | Moksture Content, % | Dry Density od | Unconfined Compressive Seength | Material Description* | Graphic | SOSI | Water Level | Depth |
| | 0- | | П | | | | T | 12* GRAVEL SURFACING Dark brown and brown mixed sixty lean clay, | ₩ | CL. | Н | 472 |
| 1 | | 1 | ST | | 17.6 | | 3870 | damp to moist FILL (Firm Silty Clay) | * | | | 412 |
| 464 | | 2 | sT | | 21.8 | 104 | 5300 | | ※ | a | | _1 <u>1</u> |
| 1 | - 16 | 3 | 5T | | 19.8 | 94 | 2450 | Very dark brown silly lean clay, moist COHESIVE ALLUVIUM (Sulf Silry Clay) Very dark gray silty clay, very moist | | CL | | 15.5 457.5 |
| - | - | . <u>4</u> . | SŢ | | 35.7 | 77 | 830 | Light gray-brown near 21'-24.3' | | | | |
| 448 | | 5 | \$ T | | 28.8 | 94 | 2580 | Gray below 24.5 COHESIVE ALLIJVIUM (Soft Silty Clay) | | | 7 | |
| - | - 32 | | | | | | } | Gray fine to coarse sand, with gravel, saturated GRANULAR ALLUVIUM | | SP | - | 30 443 |
| 1 | . | | H | | | |]] | (Gravelly Sand) | 9 | CL. | Ļ. | 35.5 437.5 |
| 432 | - | İ | | | | | | Dark gray sandy lean elay, trace gravel, moist to very noist GLACIAL TILL (Very Firm Sandy Glacial Clay) | | | | 46 |
| 1 | - 48 | | • | | | | | Gray silty fine sand, saturated GLACIAL OUTWASH (Silty Sand) | | SM | | 427 50 |
| 1 | - | | | | | | | Dark gray sandy fean clay, ir. gravel, moist | | cr | | 423 |
| 416- | - | | | | | | | GLACIAL TELL (Very Firm Sandy Glocial Clay) | | | | İ |
| 1 | -64 | | | | | | | End of Boring | 12 | 1 | - | 65 408 |
| The stratification inter represent the approximate boundary times between majorial types: ansitu, the transition may be gradual. | | | | | | | | | | | | |
| ПФ; at | 1 | Wate | | lOb | ervet hrs. | | _ days | ALLENDER BUTZKE ENG | | | S | , INC. |
| epth to | | n. V | | _ | n. ¥ | | _ n. ₹ | Geotechnical - Environmental - Con | stru | ction | Q. | C. |

| | NG I | | | | | _ | 2 | STATION | <u> </u> | hollect | No. | : <u>641343</u> | |
|------------------|-----------|------------|------------|----------|------------------------|-------------|--|--|-------------------------|-----------------|----------|-----------------|-----------------|
| t/ect | | 6, T8 | 3N, R | 46 V, | Perre | lke T | PD. | Chera: Calhous-Burns and 1801 Fuller Road | | <u></u> | 7 | ١. | 7 |
| | | ford | Coun | ty, Rey | | | | West Dea Moines, I | | ! | <u> </u> | | _4 |
| iuriso Istum | • E)evi | ston: | — <u>.</u> | M# 2 | 47. • 471. | 2,51 73' | | Date Drilled: 6-30-04 Drilling Depth, fl.: 81 | Drilling Meth Page:t | nod: <u>HSA</u> | _ | | |
| Elevation ft. | Dept. | Sample No. | Type | SPT topi | Molskure Content, % | | Unconfined Compressive Strength Est | Material Dosc | cription* | Graphic | 283 | Water Level | Depth |
| - | 0 | | | | | | | 3° GRAVEL SUI | | | Ħ | Ħ | 0.5 472 |
| - 164 – , | - 16 | | | | | | | BRIDGE DECK TO | O GROUND | | | | |
| | - - | | | | | : | | Brown fine to coacse sand GRANULAR AS (Coarse Sa | LUYIÚM | ket 👸 | SP | ¥. | 19.25 453.25 |
| -448 | - | 1 | ŞS | 4 | 11.6 27.5 | | | Very dark gray silty clay, | very moist to w | 4 | cī. | Ť | 25.5 447 |
| - | - 32 | 2 | SS | 18 | | | | COHESIVE ALI (Soft Silty C Wood noted near 30' | | | | | . 34 |
| - | | 3 | 53 | 9 | 20.1 | | | Dark gray sandy lean clay to very moist GLACIAL | | wist | CL | | 438.5 |
| 132 - | | 4 | S\$ | 13 | 17,7 | | | (Very Firm Sandy C | | | | | 44 |
| | - 48 | 5 | SS | 15 | 17.3 | | | Gray silty fine sand, satur GLACIAL OUT (Silty San | LMYZH | | SM | | 428.5 |
| | | 6 | 88 | 22 | 16.4 | | | Dark gray sandy lean clay | r, tr. gravel, moi | sı // | CL | H | 51 421.5 |
| \$16~ | - | 7 | 55 | 20 | 15.8 | | | GLACIAL ² (Very Firm Sandy C | | | | | |
| | -64 | | 52 | 22 | 15.6 | | | | | | | | 65 |
| | | 10 | 22 | 26 | 17.4 | | | Yellow brown-gray sandy gravel, damp to moist | fat clay, trace | | CH | | 407.5 |
| 1 0 0 | | 11 | 55 | 28 | 19.4 | | | GLACIAL* (Very Firm Olac | | | | | |
| ļ | - 80 | 12 | SS | 22 | 20.3 | | | | | 2 | | | 8L : |
| | L_ | <u> </u> | | | L. | <u> </u> | | End of Boring | | L | | L | 391.5 |
| The | tratifica | | | | i the eg servati | | nate bouncie | y šnao between maleris) types: i | | | | _ | |
| 16: 1 | compl | | | | | | days | ALLENDER BU | UTZKE E | NGIN | EEI | ß, | INC. |
| er: | | n. P | | | ı. ∓ | | - t. 子 | Geotechnical - Envi | | | - 1 | | - |

| Toject: | Sec. 1 | 6, 18 | SN, R | 40W | Рим | Mae Ţr | тр. | Clerk: Calboan-Burns and Associated Patter Road | | =[| 7 | Ī | 7 | Ī |
|---------------------|--------------|-----------------|------------|---------|-----------------------|--------------------|---------------------------------------|--|---|---------|----------|-------------|--------------------|------------------|
| Surtace | Craw | | | ty, for | 78 47. | - | | West Des Moines, Iowa 5 Oute Onlied: 7-1-44 D | | _ل_ | | | | |
| Suriace Datum: | | won: | | M# 2 | = 471. | | | | irithing Method: : tage: <u>1</u> of | 11 | ra . | | | |
| Generation #. | Depth ft. | Sample No. | Type | SPTbp | Moisture Content % | Dry Denatty pdf | Unconfined Compressive Strength | Majerial Descriptio | วก้ | Graphic | nscs | Water Level | Oepth | Elewation ft. |
| | 0 | | | | Г | Π | | 30" GRAVEL SURFAC | CING | | | П | 2.5 | |
| 464 | - | | | | | | | Park brown and brown mixed s damp to moist | şîjty lean clay, | | CT. | | 469.9 | - |
| • | -16 | | | | | , | | (Firm Silty Clay) Wood noted near 11' Brown and dark brown mixed b | | | | | 18 | - |
| 1 | | | | | | | | Very dark gray silty clay, very r | | | CL | | 454.4 | , . |
| 448 – - | _ | | | | | | | COHESIVE ALLUVIII (Soft Silty Clay) Very sandy and wet below 24 | UM | | | | 29 | |
| - | - 32 | | | | | | | Dark gray fine to coarse sand, v saturated GRANULAR ALLUV (Gravelly Sand) | with grave), TUM | | SP | \$ | 443.4 | - - |
| 432- | - | | | | | | | Dark gray sandy lean clay, trace to very moist | e gravel, moist | | CL | | 37 435 <i>A</i> | · . |
| - | →48 | | | | | | | GLACIAL TILL (Very Firm Sandy Giscia | | | | | 54 | - |
| 416- | - | | | | | | | Gray silty fine sand, saturated GLACIAL OUTWA: (Silty Sand) | SH | | SM CL | | 418.4 57 | _ |
| | - 64 - | |] | | | | : ! | Dark gray sandy lean clay, trace GLACIAL TEL (Very Firm Sandy Glacia | | | C. | | 413. | · - |
| 400- | | | | | | | | Yellow brown-gray sandy fat of gravel, damp to moist | - | | СН | H | 70 402.4 | 4 - |
| | | | | | | | | GLACIAL TILL (Very Firm Glacial Ci Bod of Boring | lay) | 762 | | \parallel | 75 397.4 | 4 |
| The e | Vetifica | eon ili Wale | r Lev | al Oh | t the a serval | pproxim | naie bounda | ry fines between material types: In-situ, | | | | | | _ |
| ime: et lepth to | t compl | | | | sorvan hrs. | | days | ALLENDER BUTZ | KE ENG | INI | CEI | S, | IN | C. |

| BORII Yojeci: | | | | | - | _ | 4 | STATION 117+00 71 RT Project No.: 041 |
|------------------|------------|------------|------------|---------|----------------------|--------------------|---------------------------------------|--|
| rojoui: | Sec. 16 | | | | | be T | MB. | 1901 Paller Road |
| | Crawl | | | | | | | West Des Molaes, Town 50265 |
| Surface | | | | | 472 | | | Date Orifled: 6-36-84 Drifling Method: HSA |
| Dalue: | | | B | H# 2 | 471.7 | T. | | Orifling Depth, ft.: 71 Page: 1 of E |
| Elevation ft. | eg-≓ | Semple No. | Type | SPTtpsf | Mosture Content % | Dry Densaty Pod | Uncontined Compressive Strength | Material Description descripti |
| \neg | 0 | \neg | \neg | | Н | _ | ···- | 12" GRAVEC SURFACING 105 1 |
| - 1 | . 1 | ŀ | | | | | | Dark brown, dark gray and brown mixed silty CL 471.3 |
| Į | ŀ | 7 | S 3 | 16 | 19.8 | | | lean clay, damp |
| ŀ | . | ∸ٲ | | •• | 13.6 | | | (Firm Silty Clay) CL 466.3 |
| 464 | | ļ | | | | | I | Very dark brown silty lean clay, moist to very 9 |
| 1 | · [| 2 | S 3 | 5 | 27.5 | | | moist CDHESIVE ALLUVIUM CL 463.3 |
| 1 | . [| | | | | | | (Stiff Sitty Clay) |
| - 1 | Ļ | ᆛ | <u></u> | , | | | | Very dark gray silty clay, very moist |
| } | - 16 | 3_ | 5 5 | 4 | 30.8 | | | [|
| 1 | Į | J | | | | | | Light gray-brown with fine sand content |
| 1 | · | 4 | SS | 4 | 28.4 | | 1 | below 17' COHESIVE ALLUVIUM |
| 1 | . 1 | | | | | | | (Soft Silty Clay) |
| 448 | L | | | | | | | 1 100 |
| - ` } | ٠ إ | 5 | SS | 6 | 28.0 | | | Brown-gray fine to coarse sand, with gravel, EAA SP 446. |
| - 1 | | | | | | | | Brown-gray fine to course sand, with gravel, SP 446.3 |
| 1 | · | 6 | SS | 16 | 12.7 | | | GRANULAR ALLUVIUM |
| 1 | - 32 | * | | ,,, | '' | | | (Gravelly Sand) |
| ļ | | | | | | | | Dark gray sandy lean clay, trace gravel, moist CL 439. |
| f | . [| 7 | S S | 20 | 15.5 | | | to very moist |
| - 1 | . | | | | 1 I | | l | |
| 432- | ŀ | 8 | SS | 19 | 14.R | | | |
|] | · | • | .2.7 | 17 | (**-^ | | İ | |
| ł | | | | | | | | |
| ŀ | · [| 9 | SS | 19 | 14.7 | | l | Interbedded sitry fine sand seams |
| - 1 | - 48 | | | | [| | I | near 45'-57' |
| Ţ | " " | - | - | | اا | | I | |
| } | . } | īū | 22 | 22 | 14.3 | | I | GLACIAL TILL |
| 1 | | Į | | | | | I | (Very Firm Sandy Glazial Clay) |
| | 1 | ;;; j | | 741 | ارا | | I | |
| 416 | ľ | Ш | \$\$ | 29 | 14.6 | | I | ## ## ## ## ## ## ## ## ## ## ## ## ## |
| ļ | | | - | الما | | | | |
| l | · | 12 | SS | 24 | 16.3 | | i | |
| 1 | -64 | | | | | | i | |
| [| 04 | 13 | SS | 23 | 16.6 | | l | Light gray with higher clay content below 70" |
|] | . [| \neg | | | | | Į. | |
| - | Ļ | | | ١ | | | | [[28] [] |
| 1 | · | 14 | SS. | 31 | 18.4 | | I | End of Boding 401. |
| 400 - | | ل_ | | | ليا | | | |
| The # | | | | | servati | | nme bound | ary lines between meterial types: ki-silu, the transition may be oradual. |
| ime: et | | | | | bes, | *** | days | ALLENDER BUTZKE ENGINEERS, IN |
| epth to | | | _ | | | _ | _ π. Ç | Geolechnical - Environmental - Construction Q.C. |

SOUNDING DATA

(SEE "SITUATION PLAN", SHEET 3, FOR BORING LOCATIONS)

GEOTECHNICAL INFORMATION PROVIDED HEREWITH IS THE SOLE RESPONSIBILITY OF ALLENDER BUTZKE ENGINEERS, INC., WHOSE GEOTECHNICAL REPORT DATED 06-06-04, COMPLETE WITH THE LICENSED ENGINEER'S SEAL AND CERTIFICATION, IS AVAILABLE FOR VIEWING.


151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

INTERGAL ABUTMENTS 47'-5 END SPANS

PIOA PIERS 56'-6 INTERIOR SPAN


SOUNDING DATA

STATION 116+25.00 CRAWFORD COUNTY,



TOP OF SLAB ELEVATIONS


BENCH MARK #1: 60d SPIKE IN GATE POST, SOUTH SIDE OF O AVENUE ROAD, OPPOSITE FARM DRIVE ENTRANCE TO HOUSE. 112+86, 34° RT., ELEV.= 482.31
BENCH MARK #2: RAILROAD SPIKE IN POWER POLE, 1st. POLE EAST OF BRIDGE, NORTH SIDE OF O AVENUE ROAD. 118+21, 34° LT., ELEV.= 471.73



SLAB THICKNESS DETAILS

NOTE: THE SLAB THICKNESS (T) AT BEAMS IS BASED ON THE ANTICIPATED BEAM CAMBER REMAINING AFTER PLACING THE SLAB, BUT IS NOT GUARANTEED FOR CONSTRUCTION. IF BEAM IS UNDER CAMBERED, INCREASE SLAB THICKNESS (T) AT BEAMS TO COMPENSATE, IF BEAM IS OVER CAMBERED, THE SLAB THICKNESS (T) MAY BE DECREASED A MAXIMUM OF 1/2" EMBEDMENT AT THE BEAM (T1). IF MORE THAN 1/2" EMBEDMENT IS REQUIRED, OR IF THE HAUNCH EXCEEDS 23", THE GRADE LINE IS TO BE REVISED. THE ABOVE DIAGRAMS DO NOT APPLY TO THE CANTILEVERED SLAB SIDE OF THE EXTERIOR BEAM.

| • | € W. ABUT. BRG. | | | | | | € W. BEARING W. PIER | | | | | € BRIDGE | | | | | Œ E. BEARING E. PIER | | | | | [| Œ E. ABUT. BRG. | |
|--|-----------------------|--------|--------|--------|--------|--------|----------------------------|--------|--------|--------|--------|-------------|--------|--------|--------|--------|----------------------------|--------|---------|--------|--------|--------|-----------------------|----------|
| LOCATION | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | LOCATION |
| Δ | 476.23 | 476.25 | 476.29 | 476.33 | 476.39 | 476.46 | 476.54 | 476.55 | 476.64 | 476.73 | 476.83 | 476,94 | 477.06 | 477.19 | 477.33 | 477.48 | 477,51 | 477.70 | 477.89 | 478.10 | 478.31 | 478.54 | 47B.79 | A |
| | 476.26 | | 476.32 | 476.36 | 476.42 | 476.49 | 476.57 | 476.58 | 476,67 | 476.76 | 476,86 | 476.97 | 477.09 | 477.22 | 477.36 | 477.51 | 477.54 | 477.73 | 477.92_ | 478.13 | 478.34 | 478.57 | 478.82 | В |
| c | 476.36 | 476.38 | 476.42 | 476.46 | 476.52 | 476.59 | 476.67 | 476.68 | 476.77 | 476.86 | 476.96 | 477.07 | 477.19 | 477.32 | 477.46 | 477.61 | 477.64 | 477.83 | 478.02 | 478.23 | 478.44 | 478.67 | 478. 9 2 | С |
| D | 476.37 | 476.39 | 476.43 | 476.47 | 476.53 | 476.60 | 476,68 | 476.69 | 476.78 | 476.87 | 476.97 | 477,08 | 477.20 | 477.33 | 477.47 | 477.62 | 477.65 | 477.84 | 478.03 | 478.24 | 478.45 | 478.68 | 478.93 | D |
| <u> </u> | 476.39 | 476.41 | 476.45 | 476.49 | 476.55 | 476.62 | 476.70 | 476.71 | 476.80 | 476.89 | 476.99 | 477.10 | 477.22 | 477,35 | 477.49 | 477.64 | 477.67 | 477.86 | 478.05 | 478.26 | 478.47 | 478.70 | 478.95 | Ę |
| | 476.37 | 476.39 | 476.43 | | 476.53 | 476.60 | 476.68 | 476.69 | 476.78 | 476.87 | 476.97 | 477.08 | 477.20 | 477.33 | 477.47 | 477.62 | 477.65 | 477.84 | 478.03 | 478.24 | 478.45 | 478.58 | 478.93 | E |
| | 476.36 | 476.38 | 476.42 | | 476.52 | 476.59 | 476.67 | 476,68 | 476.77 | 476.86 | 476.96 | 477.07 | 477.19 | 477.32 | 477.46 | 477.61 | 477.64 | 477.83 | 478.02 | 478.23 | 478.44 | 478.67 | 478.92 | F |
| | 476,36 | | 476.32 | 476.36 | 476.42 | 476.49 | 476.57 | 476.58 | 476.67 | 476.76 | 476.86 | 476.97 | 477.09 | 477.22 | 477.36 | 477.51 | 477.54 | 477.73 | 477.92 | 478.13 | 478.34 | 478.57 | 478.82 | G |
| G | | 476.25 | | 476.33 | | | 476.54 | _ | | | 476.83 | | | | 477.33 | 477.48 | 477.51 | 477.70 | 477.89 | 478.10 | 478.31 | 478.54 | 478.79 | H |




151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE


INTERGAL ABUTMENTS 47'-5 END SPANS P10A PIERS 56'-6 INTERIOR SPAN


SUPERSTRUCTURE DETAILS

STATION 116+25.00 CRAWFORD COUNTY,

O' SKEW







GRADING NOTES

PLAN AND PROFILE SHEETS INCLUDED IN THE PROJECT ARE FOR PURPOSE OF ALIGNMENT, LOCATION AND SPECIAL DIRECTION FOR THE WORK TO BE PERFORMED UNDER THIS CONTRACT. IRRELEVANT DATA ON THESE SHEETS IS NOT TO BE CONSIDERED A PART OF THIS CONTRACT.

THE CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN ACCESS TO INDIVIDUAL PROPERTIES DURING CONSTRUCTION. RELOCATED ACCESS SHALL BE COMPLETED TO INDIVIDUAL PROPERTIES PRIOR TO REMOVAL OF EXISTING ACCESS. IF THE PERMANENT ACCESS CANNOT BE COMPLETED PRIOR TO REMOVAL OF THE EXISTING ACCESS, AN ALTERNATE ACCESS SHALL BE PROVIDED AND MAINTAINED. THIS WORK WILL BE CONSIDERED INCIDENTAL TO THE PROJECT.

STANDARD ROAD PLANS ARE AVAILABLE FROM THE IOWA DEPARTMENT OF TRANSPORTATION, HIGHWAY DIVISION, AMES, IOWA.

EXCAVATION AND BORROW

DUE CAUTION IS TO BE USED IN WORKING OVER AND AROUND ALL TILE LINES. BREAKS IN THE TILE LINE DUE TO THE CONTRACTOR'S CARELESSNESS ARE TO BE REPLACED AT HIS EXPENSE WITHOUT COST TO THE OWNER. ANY TILE LINES BROKEN OR DISTURBED BY OUR CUT LINES WILL BE REPLACED AS DIRECTED BY THE ENGINEER IN CHARGE OF CONSTRUCTION AND AT THE OWNER'S EXPENSE.

ALL PROPOSED DRIVES AND FIELD ENTRANCES SHALL BE CONSTRUCTED WITH A 20' TOP AND 3:1 SLOPES, UNLESS NOTED OTHERWISE.

151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

INTERGAL ABUTMENTS 47'-5 END SPANS P10A PIERS 56'-6 INTERIOR SPAN

GRADING NOTES AND TYPICAL SECTIONS

STATION 116+25.00
CRAWFORD COUNTY.

O' SKEW

TABULATION OF STEEL BEAM GUARDRAIL AT BRIDGE END POST, CONCRETE BARRIER AND RAILROAD SIGNALS

108-8A

| | | | | | | | | | | | | | | | Refer to St | endard Road Flans | RE-48A-9, RE-63, | RE-64A(1), RE-64 | 4A(2), | and RE-659 | l | | | | | | | | | | 10-19-04 |
|-----|-----------------------|--------------|----------------|--------------|----|-------------------------|--|----------|--------------|---------------|-------|--------------------------|------|----------------------------------|---------------------------------|---|------------------|------------------|------------------|------------|---------|----------------|------------------|--|--------|--|--------------|----------------|-------------------|---|-------------------------------|
| | | LOC | ATION | | | · · · · · i | The state of the s | | LAY | OUT LE | NGTHS | | | | MATERIALS | REQUIRED | | | DELINI | EATORS AND | OBJEC | IAM T | RKERS | BID | ITEM: | S | | | | ① Lane(s) to which the obstacle is adjace ② Applies to Standard Road Plan RE-53 o | |
| | DIRECTION GOF TRAFFIC | | = Outside Sign | | | IANDARD ROAD PLAN | @ | (18.75') | | √F Lin.Ft. | (v72) | ET Termina (37.5°) | | Transition Section (5.25') | 'w' Beam ③ (VT1)+(VF)+ (VT2)+€T | Posts @ 6"x 8"x 7' with 6"x 8" Spacer Blocks (6 or 7) No. | | with 6" x 8" | Туре | White | Type 2 | Z Typo | | Installation of Guardrall STS + (VT)+(VF) + (VT2)+(ET) Lin.Fi. | RE-331 | Anchorage and Terminal Systems RE-33B RE-694 RE-69B RE-69C RE-7 | | | | ③ includes (1) special 12.5" sections of 'n RE-75. ④ (6) 6"x 8"x 7" post required when RE- In appointed. ⑤ The lost two poets of the RE-76 Termi included as part of that bild flem. | W' Beam, see -63 or RE–69C |
| ⊢ | | 13. | _ | | - | | 100, | | | | | | | | | | 7 | | | _ | - | ═ | , | 68.75 | _ | | + - | † , | + | 1 WEST END, RT. | |
| L | 1 E. | A | 0 | 116+25 | 00 | RE-648 | - | 18.75 | | 12.5 | | 37.5 | 25.0 | 6.25 | 50.0 | | 3 | <u> </u> | - ' - | | <u></u> | ↓ - | ' | | _ | + | | + - | - - ' | | |
| Г | 2 W. | 7 | 0 | 116+25 | 00 | RE-64B | _ | 18.75 | - | 12.5 | - | 37.5 | 25.0 | 6.25 | 50.0 | 8 | 3 | 5 | 1 | <u> </u> | 2 | | - | 68.75 | | | | ' | | 1 WEST END, LT. Δ | |
| _ F | 3 W | 1 4 | 0 | 116+25 | 00 | RE-64B | | 18.75 | - | 12.5 | _ | 37.5 | 25.0 | 6.25 | 50.0 | 6 | 3 | 5 | 1 | _ | 2 | | 1 | <i>68.75</i> | - | - | - | 1 | _ ! | 1 EAST END, LT. A | |
| r | 4 E. | 17 | _ | 116+25 | _ | RE-648 | | 18.75 | | 12.5 | | 37.5 | 25.0 | 6.25 | 50.0 | 6 | 3 | 5 | 1 | - | 2 | . 1 | - | 68.75 | - | _ | | 1 | | 1 EAST END, RT. | . <u>.</u> |
| _ F | | | - | | - | | - ' | | | İ | | | | | | | | · · | | | | | | | | ŀ | | l | | | |

NOT A BID ITEM
 DEFLECT INSTALLATION LINE 1'3' AT END OF OPEN RAIL/BEGINNING OF END POST.

| © Lane(s) to which the installation is adjacent. TABULATION OF GRADING FOR GUARDRAIL INSTALLATIONS ORder to Standard Road Plans RL-12, RL-14, and Typicals 4303 or 4306 | | | | | | | | | | | | 107-23 04-27-99 | | | | | | | | |
|---|------------|-----------|----------------|--------------|------|------|------|------|---------|---------|----------|--------------------|---------|------------|--|----------|------|------|--------|---------|
| LOCATION POINT | | | | DIMENSIONS @ | | | | | | | PIPE | | | | | | | | | |
| No. | OF TRAFFIC | | RECTION G | Station | SIDE | SIDE | SIDE | SIDE | SIDE | TYPE | (€ Fe | - | Fe | Z) of | | IN PLACE | Size | Туре | Length | REMARKS |
| | ᆵ뇽 | | | | A | T | A | T | Cu.Yds. | Çu.Yds. | Inches | | Lin.Ft. | | | | | | | |
| 1 | E. | 114+75.39 | - | 1 | 10.1 | 1 | 58 | | 153 | ı | | - | _ | W. END RT. | | | | | | |
| 2 | W. | 114+74.18 | | 1 | _ | 7.4 | - | 45 | 75 | _ | - | | - | W. END LT. | | | | | | |
| 3 | W. | 117+75.82 | <u> </u> | 7 | 7,4 | - | 48 | _ | 139 | _ | 1 | _ | | E. END LT. | | | | | | |
| 4 | E. | 117+74.61 | - " | 7 | - | 10.1 | ı | 58 | 238 | - | - | 1 | - | E. END RT. | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |

A INCLUDES 35% FOR SHRINKAGE

| | • | TABUL | ATION | OF ER | OSION | CONTR | OL FEA | ATURES | 100-19 11-10-83 |
|----------------------------|---|-------|---------------------------|-------|------------------------|--------------|---------------------------|----------------------------|--------------------|
| | OCATION | | · · | | <u> </u> | | | | |
| LOCATION O STATION T | R | SIDE | FOR DITCH CHECK | | SILT BASIN (No.) | SILT DIKE | SILT DITCH (UN.FT.) | SILT FENCE (LIN.FT.) | REMARKS |
| TÒ BE DE | (EXACT LOCATION TO BE DETERMINED BY THE ENGINEER) | | SILT FENCE (UN.FT.) | | | | | | |
| 113+40.00 | | R/L | 20/20 | , | | _ | | - | |
| 115+40.00 | <u> </u> | R/L | 20/20 | _ | - | | _ | - | 1 |
| 116+80.00 | 118+70.00 | R | | - | | | - | 210 | - |
| 116+80.00 | 118+90.00 | L | | | | - | - | 230 | 1 |
| 119+60.00 | 121+20.00 | L | _ | , | - | | - | 180 | ı |
| 119+60.00 | 121+40.00 | R | | - | | | <u> </u> | 200 | - |
| | | | | | | | | | |

| REMOVAL OF | EXISTING STRUCTURES | 110-2 10-13-72 |
|--------------------|---|-------------------|
| LOCATION | DESCRIPTION | DISPOSAL |
| 112+75.00, 25° RT. | 30" Ø x 30' C.M.P. * | CONTRACTOR |
| 112+75.00, 28' LT. | 24" ø x 25' R.C.P. * | CONTRACTOR |
| 116+03.00 | 116' x 20.2' PONY TRUSS WITH I—BEAM APPROACHES | CONTRACTOR |

^{*} INCIDENTAL TO CLASS 10 ROADWAY & BORROW

| | SUM | /ARY | OF I | EARTH | WOR | K | | | |
|-----------|--------------|--|---------------------|--|-------|------------|------------------|--|--|
| STATION | | I \$0. FT. | VOLUMES IN CU. YDS. | | | | | | |
| | CUT | FILL | СИТ | ADD'L CUT | FILL | ADD'L FILL | ∩ L 1+35X | | |
| 12+25.00 | 0 | 0 | 105 | | 14 | | 19 | | |
| 112+75.00 | 113 | 15 | 69 | | 25 | 153 | 240 | | |
| 13+00.00 | 35 | 40 | 287 | | 237 | 100 | 320 | | |
| 114+00.00 | 120 | 88 | 455 | | 438 | | 591 | | |
| 115+00.00 | 125 | 148 | 101 | 87 | 198 | 169 | 496 | | |
| 115+30.00 | 57 | 208 | 101 | | 198 | | 197 | | |
| BRIDGE | | | | Δ235 | | 146 | | | |
| 117+20.00 | 0 | 563 | 1—_ | +524 | 0.505 | 417 | 563 | | |
| 18+00.00 | 0 | 790 | <u> </u> | *12,524 | | | 2,707 | | |
| 119+00.00 | 0 | 727 | 0 | △1,505 | 2,810 | 279 | 4,170 | | |
| 119+30.00 | 0 | 499 | 0 | | 681 | | 919 | | |
| 120+00.00 | 10 | 505 | 0 | | 1,302 | 1,519 | 3,808 | | |
| 121+00.00 | 149 | 229 | 276 | | 1,359 | | 1,835 | | |
| 121+50.85 | 0 | 0 | 140 | | 216 | 112 | 443 | | |
| 127+30.03 | + - | ۰ | | | | | | | |
| | | | _ | : | | | | | |
| | | | - | | | | | | |
| | - | | $\overline{}$ | | | | | | |
| | | | $\overline{}$ | | | | | | |
| | ⊢ | | lacksquare | | | | | | |
| | | | \vdash | | | | | | |
| | TOTAL | | 1,433 | 14.875 | 9,285 | 2,795 | 16,308 | | |

^{*} BORROW

A CLASS 10 CHANNEL.

TRAFFIC CONTROL PLAN

THE PROJECT ROUTE WILL BE CLOSED TO TRAFFIC. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, SIGNING, AND PAVEMENT MARKINGS INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATIVE CODE (IAC) CHAPTER 130.

PLASTIC SAFETY FENCE SHALL BE PLACED ON BOTH SIDES OF THE BRIDGE SITE. IN ADDITION, A TYPE III BARRICADE SHALL BE PLACED IN ADVANCE OF THE PLASTIC SAFETY FENCE, A "ROAD CLOSED" SIGN (R-11-2, 48" x 30") SHALL BE PLACED ON EACH TYPE III BARRICADE ALONG WITH TWO TYPE "A" LOW INTENSITY FLASHING WARNING LIGHTS.

THE CRAWFORD COUNTY MAINTENANCE SHALL SALVAGE ALL ROAD MARKERS AFTER ROAD IS CLOSED.

THE BID ITEM "TRAFFIC CONTROL" SHALL INCLUDE THE COST FOR ALL TRAFFIC CONTROL MEASURES REQUIRED OF THE CONTRACTOR EXCEPT FOR THOSE WHICH ARE SEPARATE BID ITEMS OR ARE INCIDENTAL TO OTHER BID ITEMS.

THE GUARDRAIL INSTALLATION MUST BE COMPLETED BEFORE THE ROAD IS OPENED TO TRAFFIC.

ALL CONTRACTOR FURNISHED TRAFFIC CONTROL SIGNS USED ON THIS PROJECT SHALL BE SHEETED WITH ENCAPSULATED LENS SHEETING.

TYPE 'C' STEADY BURN WARNING LIGHTS ARE NOT REQUIRED FOR VERTICAL PANELS, BARRICADES, AND DRUMS WHEN THESE TRAFFIC CONTROL DEVICES ARE SHEETED WITH ENCAPSULATED LENS SHEETING.

| POINTS OF ACCESS (RL-7) Refer to Detail Cross Sections. For Pipe Culvert, Details Refer to RF-30A, RF-30B, and RF-30C. | | | | | | | | | |
|---|------|----|------|--------|------------------|------------------|------------------|----------|--------------------|
| LOCATION | | | | LENGTH | | 400011 | SURFACE | | |
| STATION | SIDE | ⊗ | TYPE | · · · | SIZE (INCHES) | LT. (LIN.FT.) | RT. (LIN.FT.) | (NO.) | MATERIAL (TONS) |
| 112+75.00 | LT. | 20 | С | 2.0 | 24 | 15,5 | 23.5 | 2 | 10 |
| 112+75.00 | RT. | 20 | | 1.5 | 30 | 22.4 | 16.4 | 2 | - |
| 119+30.00 | LT. | 20 | С | - | - | . – | - | ı | - |
| 119+30.00 | RT. | 20 | C | - | - | - | - | <u> </u> | |

| TABULATION | OF SAFE | TY CLOSU | RES 108-13A 10-28-97 | | | | | | |
|--|-----------|-------------|-------------------------|--|--|--|--|--|--|
| Refer to Section 251B of the Standard Specifications | | | | | | | | | |
| STATION | CLOSUR | E TYPE | REMARKS | | | | | | |
| SIATION | Road Qty. | Hazard Qty. | KEMAKKS | | | | | | |
| 111+00 | 1 | _ | WEST END | | | | | | |
| 114+50 | 1 | 1 | WEST END | | | | | | |
| 117+50 | _ | 1 | EAST END | | | | | | |
| 121+00 | 1 | - | EAST END | | | | | | |
| | | | | | | | | | |

151'-4 x 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

INTERGAL ABUTMENTS 47'-5 END SPANS

P10A PIERS 56'-6 INTERIOR SPAN

TABULATIONS

STATION 116+25.00 CRAWFORD COUNTY,

