06/09/2008 @02:29PM PLC PLAT CORNER CER Book: Page: Total Fees: \$7.00

Book: Total Fees:

Pages: 1

WILKE LAND SURVEYING INC.

401 1800th Street

Panama, Iowa 51562

(712)489-2898


UNITED STATES PUBLIC LAND SURVEY CORNER CERTIFICATE


CRAWFORD SECTION 19 TOWNSHIP 83N RANGE 41W COUNTY_

Survey of LOT 1 of the NW1/4 SE1/4 Certificate Prepared For:___ (No Corner Certicates exist for these Corners)

Monument Description and Remarks:

- (1)—No monument was set at this Corner as the WPA notes state. Set ½" dia. by 24" rebar w/orange cap PLS #17048 (0.5' deep) in a eroded gully on line with fence South and North but approx. 18' South of Corner Post for fence East. The fence at the top of hill East was held for line from the found SE Corner of Section 19 and the line was projected West to intersect with the North South fence. The East fence clearly deflects Northwesterly as it comes West down the hill.
- (2)— Set 5%" dia. by 24" rebar w/orange cap PLS #17048 (0.3' deep) at the projected intersection of fences from the North and West.
- (3)— Dug for WPA monument but found nothing. Set % dia. by 24" rebar w/orange cap PLS #17048 (0.3' deep) at the center of road and in line with the fence West.






I hereby certify that this land surveying document was prepared and the related survey work was performed by me or under my direct personal supervision and that I am a duly licensed Land Surveyor under the laws of the State of lows.


ean Dean A. Wilke


License number 17048

My license renewal date is December 31, 2009

Pages or sheets covered by this seal: This page only







	Corners Section	to be Inde	exed Range
S1/4 CORNER	19	83N	41W
CENTER	19	83N	41W
E1/4 CORNER	19	83N	41W